THE COLLINGS FOUNDATION

SITE DEVELOPMENT PLAN

137 BARTON ROAD, STOW, MASSACHUSETTS 586 MAIN STREET, HUDSON, MASSACHUSETTS JANUARY 20, 2015

PREPARED FOR:

COLLINGS FOUNDATION, INC. P.O. BOX 248 STOW, MA 01775

PREPARED BY:

ANDREWS SURVEY & ENGINEERING, INC. 104 MENDON STREET P.O. BOX 312 UXBRIDGE, MA 01569 P: 508.278.3897 F: 508.278.2289

GENERAL CONTRACTOR:

J.M. COULL, INC. 20 POWDER MILL ROAD MAYNARD, MA 01754

P: 978.461.0330 F: 978.461.0275

ARCHITECT

F: 978.244.1191

AHP ARCHTECTS 20 CHELMSFORD STREET CHELMSFORD, MA 01824 P: 978.244.1100

LANDSCAPE ARCHITECT



280 BEVERLY ROAD WORCESTER, MA 01605 P: 508.852.2644

TRAFFIC:

CONLEY ASSOCIATES, INC. **40 WARREN STREET BOSTON**, MA 02129 P: 617.742.5111 F: 617.742.5333

ENVIRONMENTAL:

GODDARD CONSULTING, LLC 14 WILSON ROAD NORTHBOROUGH, MA 01532 P: 508.525.0726

I. NOTICE TO CONTRACTOR: THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF EXISTING UTILITIES AND STRUCTURES AS SHOWN ON THESE PLANS IS BASED ON RECORDS OF VARIOUS UTILITY COMPANIES AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THIS INFORMATION IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE THE LOCATION OF ALL UNDERGROUND UTILITIES AND STRUCTURES SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR MUST CONTACT THE APPROPRIATE UTILITY COMPANY, ANY GOVERNING PERMITTING AUTHORITY, AND "DIGSAFE" AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION WORK TO REQUEST EXACT FIELD LOCATION OF UTILITIES. THE ENGINEER SHALL BE NOTIFIED IN WRITING OF ANY UTILITIES INTERFERING WITH THE PROPOSED CONSTRUCTION AND APPROPRIATE REMEDIAL ACTION SHALL BE TAKEN BEFORE PROCEEDING WITH THE WORK. IT SHALL BE THI RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THE PLAN.

2. PROPERTY LINE INFORMATION IS A RESULT OF PARTIAL FIELD SURVEY AND A COMPILATION OF AVAILABLE PUBLIC RECORDS.

3. TOPOGRAPHY TAKEN FROM AERIAL PHOTOGRAPHY COMPILED BY EASTERN TOPOGRAPHICS, ON APRIL 7, 2014. GROUND CONTROL PROVIDED BY ANDREWS SURVEY & ENGINEERING, INC. DATUM: MASS. STATE PLAN

4. MAP U-2, PARCEL 54 AND MAP R-25, PARCEL 16A OWNED BY ROBERT & CAROLINE COLLINGS TO BE CONVEYED TO COLLINGS FOUNDATION, INC. UPON APPROVAL.

OWNERS OF RECORD: ROBERT F. & CAROLINE J. COLLINGS 137 BARTON ROAD STOW, MA 01775

COLLINGS FOUNDATION, INC. P.O. BOX 248 STOW, MA 01775

MAYNARD SAND & GRAVEL, INC. C/O QUINN BROS. CORP. 3 CALDWELL DRIVE AMHERST, NH 03031

STOW ASSESSORS INFORMATION: MAP U-2, PARCEL 54 MAP R-25, PARCELS 13, 16A, 16B, 17

AREA: 89± ACRES HUDSON ASSESSORS INFORMATION: MAP 35, PARCEL 3

STOW ZONING INFORMATION: ZONE: RESIDENTIAL DISTRICT MINIMUM AREA: 65,340 S.F.

AREA: 10± ACRES


MINIMUM FRONTAGE: 200' SETBACKS: FRONT 30', SIDE 25', REAR 40'

HUDSON ZONING INFORMATION: ZONE: INDUSTRIAL (M-6) MINIMUM AREA: 60,000 S.F.

MINIMUM FRONTAGE: 150' SETBACKS: SIDE 20', REAR 20', 35% O.S.

DEED REFERENCES: BK. 13361, PG. 267 BK. 55607, PG. 530 BK. 12747, PG. 438

PLAN REFERENCES: PLAN 66 OF 1944, PLAN 1653 OF 1956 PLAN 841 OF 1977, PLAN 41 OF 1973 PLAN 434 OF 2001, PLAN 183 OF 1993



SHEET

C-0.0

C-1.0

C-1.1

SHEET

TITLE

COVER SHEET

SITE COMPOSITE PLAN

EXTERIOR ELEVATIONS

GOVERNMENT & UTILITY CONTACTS

STOW PLANNING DEPARTMENT STOW CONSERVATION COMM. 380 GREAT ROAD 380 GREAT ROAD

A.202

P: 978.897.5098 F: 978.897.2321 ATTN: KAREN KELLEHER, TOWN PLANNER

16 CRESCENT STREET P: 978.897.4537 F: 978.461.1400

STOW FIRE DEPARTMENT

DRAWING

DATE

1/20/15

1/20/15

1/20/15

4/23/14

LATEST

5/18/15

5/18/15

5/18/15

REVISION

ATTN: JOE LANDRY, CHIEF

STOW BOARD OF HEALTH 380 GREAT ROAD P: 978.897.4592 F: 978.897.4615 ATTN: JACK WALLACE, AGENT

HUDSON FIRE DEPARTMENT 296 COX STREET P: 978.562.5565 F: 978.568.9609 ATTN: JOHN M. BLOOD, CHIEF

HUDSON BUILDING DEPARTMENT 78 MAIN STREET P: 978.568.9625

F: 978.562.8508

ATTN: JEFFREY WOOD, BUILDING COMM.

P: 978.897.8615 F: 978.897.4534 ATTN: KATHY SFERRA, COORDINATOR

ATTN: WILLIAM BOSWORTH, CHIEF

STOW POLICE DEPARTMENT 305 GREAT ROAD P: 978.897.4545 F: 978.897.3692

HUDSON PLANNING DEPARTMENT 78 MAIN STREET P: 978.562.9963 F: 978.568.9641

ATTN: JENNIFER BURKE, PLANNING DIRECTOR

HUDSON POLICE DEPARTMENT **62 PACKARD STREET** P: 978.562.7122

ATTN: DAVID A. STEPHENS. CHIEF HUDSON BOARD OF HEALTH

F: 978.568.9660

78 MAIN STREET P: 978.562.2020 F: 978.562.8508 ATTN: SAM WONG, DIRECTOR

STOW BUILDING DEPARTMENT 380 GREAT ROAD

LOCUS MAP

VEHICULAR & PEDESTRIAN CIRCULATION PLAN

P: 978.897.2193 F: 978.897.7258 ATTN: CRAIG MARTIN, BUILDING COMM

STOW HIGHWAY DEPARTMENT 88 SOUTH ACTON ROAD P: 978.897.8071 F: 978.897.5682 ATTN: MICHAEL CLAYTON, SUPT.

HUDSON CONSERVATION COMM 78 MAIN STREET P: 978.562.2020 F: 978.562.8508 ATTN: DEBBIE CRAIG, ADMINISTRATOR

HUDSON D.P.W. 1 MUNICIPAL DRIVE P: 978.897.8071 F: 978.897.5682 ATTN: ANTHONY MARQUES, DIRECTOR

HUDSON LIGHT AND POWER DEPT 49 FOREST AVENUE P: 978.568.8736 F: 978.562.1389

VERIZON COMMUNICATIONS 1.800.870.9999


P: 508-278-3897 F: 508-278-2289 Survey & Engineering, Inc. and shall not be altered o reused in whole or part without the express written permission of Andrews Survey & Engineering, Inc. APPROVAL UNDER SITE PLAN REVIEW. STOW PLANNING BOARD


BEING A MAJORITY

UNDATION, 30X 248 MA 01775 CHE COLLINGS
SITE DEVELO
137 BART
STOW, M INGS P.(

REVISIONS DESCRIPTION 4/22/15 PER REVIEW COMMENTS 2 5/18/15 PER REVIEW COMMENTS ...\dwg\2014-021_SP-R6.dwa DRAWN BY

CHECKED BY JANUARY 20, 2015 PROJECT NO. | 2014-021






P.E. SHEET TITLE


COVER SHEET


C - 0.0


PLAN NO. L-4403


DRAWING NO.
































EROSION AND SEDIMENT CONTROL REQUIREMENTS

PART 1 - GENERAL

1.01 SUMMARY

A. FURNISH, INSTALL, AND MAINTAIN TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL MEASURES, SUCH AS, BUT NOT NECESSARILY LIMITED TO, STRAW BALE AND SILT FENCE BARRIERS, RIPRAP, VEHICLE TRACKING PADS, DIVERSION CHANNELS AND BERMS, CHECK DAMS, STRATEGICALLY LOCATED STOCKPILES, SEDIMENT BASINS, MULCH, AND SEED MIX (HEREINAFTER "CONTROL MEASURES") ADEQUATE TO PREVENT THE CONVEYANCE OF EROSION PRODUCTS (E.G. SOIL, MULCH, SOD) OFF SITE, OR INTO ENVIRONMENTALLY SENSITIVE AREAS, OR INTO AREAS WHERE WORK WILL BE ADVERSELY IMPACTED. ENVIRONMENTALLY SENSITIVE AREAS INCLUDE, BUT ARE NOT NECESSARILY LIMITED TO, WETLANDS, TRIBUTARIES TO WETLANDS, WETLAND BUFFER ZONES, INTERMITTENT AND PERENNIAL STREAMS / RIVERS, AND THEIR ATTENDANT BUFFER ZONES.

ALL METHODS AND MATERIALS USED FOR EROSION CONTROL SHALL CONFORM TO THE REQUIREMENTS SET FORTH IN "EROSION AND SEDIMENT CONTROL GUIDELINES FOR URBAN AND SUBURBAN AREAS A GUIDE FOR PLANNERS, DESIGNERS, AND MUNICIPAL OFFICIALS" AS PUBLISHED BY THE MASSACHUSETTS DEPARTMENT OF ENVIRONMENTAL PROTECTION, BUREAU OF RESOURCE PROTECTION, UNLESS OTHERWISE APPROVED IN WRITING.

1. REFER TO DRAWINGS FOR LOCATION AND DETAILS OF LIMITS OF DISTURBANCE AND CONTROL MEASURES REQUIRED TO COMMENCE WORK. LIMITS OF DISTURBANCE SHALL BE MARKED WITH TAPE, SIGNS, OR ORANGE CONSTRUCTION FENCE PRIOR TO COMMENCING ANY LAND DISTURBANCE ACTIVITIES. CONTROL MEASURES WILL BE ADEQUATE ONLY FOR VEGETATION CLEARING. THE DRAWINGS ARE NOT INTENDED TO GRAPHICALLY DEPICT ALL CONTROL MEASURES THAT WILL BE REQUIRED TO MEET THE REQUIREMENTS DESCRIBED IN 1.01.A.

2. DEVISE AND EMPLOY CONTROL MEASURES THROUGHOUT THE DURATION OF PROJECT, OVER ALL AREAS DISTURBED OR UNDISTURBED BY CONSTRUCTION, AS NECESSARY TO MEET THE REQUIREMENTS DESCRIBED IN 1.01.A.

3. DEVISE AND EMPLOY TEMPORARY CONTROL MEASURES AS NECESSARY TO MEET THE REQUIREMENTS DESCRIBED IN 1.01.A, WHILE ALLOWING WORK TO PROCEED IN AN EFFICIENT, COST EFFECTIVE MANNER.

4. DEVISE, EMPLOY AND MAINTAIN CONTROL MEASURES UNTIL SUCH TIME AS THE ENTIRE SITE IS PERMANENTLY STABILIZED BY ESTABLISHED VEGETATION, FINISH LANDSCAPE MATERIALS, PAVED SURFACES, AND/OR ROOF AREA.

5. ONCE THE SITE IS PERMANENTLY STABILIZED AND CERTIFIED AS SUCH BY ENGINEER, REMOVE TEMPORARY CONTROL MEASURES WHILE PROTECTING STABILIZED SURFACES.

1.02 SUBMITTALS

A. SUBMIT PRODUCT DATA, WARRANTY, AND TEST REPORTS AS INDICATED ON THE DRAWINGS.

B. SUBMIT SKETCH SHOWING LOCATIONS OF PROPOSED STOCKPILE AREAS, CONSTRUCTION ENTRANCES AND EROSION CONTROLS IF NOT SHOWN ON THE SITE PLAN OR DIFFERENT FROM THOSE LOCATIONS SHOWN ON THE SITE PLAN.

C. A SITE SPECIFIC SEQUENCE OF CONSTRUCTION FOR EACH PORTION OF THE SITE. NO PORTION OF THE SITE SHALL EXCEED FIVE (5) ACRES.

1.03 QUALITY ASSURANCE

A. COMPLY WITH GOVERNING CODES AND REGULATIONS. PROVIDE PRODUCTS FROM ACCEPTABLE MANUFACTURERS. USE EXPERIENCED INSTALLERS. DELIVER, HANDLE, AND STORE MATERIALS IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.

B. CONFORM TO CONDITIONS OF APPROVAL ISSUED BY REGULATORY AGENCIES INCLUDING, BUT NOT NECESSARILY LIMITED TO, LOCAL PLANNING BOARD, CONSERVATION COMMISSION, CITY COUNCIL, BOARD OF HEALTH, PUBLIC WORKS / HIGHWAY DEPARTMENT, STATE ENVIRONMENTAL PROTECTION DEPARTMENT, AND U.S. GOVERNMENT, ENVIRONMENTAL PROTECTION AGENCY. WHERE CONDITIONS OF REGULATORY APPROVAL DIFFER FROM REQUIREMENTS CONTAINED HEREIN OR ON THE DRAWINGS, COMPLY WITH THE MORE STRINGENT REQUIREMENT.

PART 2 - PRODUCTS

2.01 MATERIALS

A. STRAW BALES: WEED FREE DRY GRASS OR STRAW, MACHINE BOUND WITH JUTE OR WIRE, APPROXIMATE SIZE EACH BALE 42" X 16" X 16". EACH BALE SHALL BE STAKED WITH A MINIMUM OF TWO 24" LONG HARDWOOD STAKES. NOTE: STRAW SHALL NOT BE USED.

B. STRAW WATTLES: NORTH AMERICAN GREEN MODEL WS1210 OR APPROVED EQUAL.

C. SILT FENCE: NON-WOVEN, UV-RESISTANT, POLYPROPYLENE FABRIC, FLOW RATED AT 10 GPM/SF MINIMUM, GRAB TENSILE RATED AT 124 POUNDS MINIMUM, WITH INTEGRAL STAKE LOOPS, AND HARDWOOD STAKES. USE NO. 2130 BY AMOCO FABRICS & FIBERS, OR APPROVED EQUAL.

D. MULCH: ORGANICS INCLUDING STRAW, PROCESSED PINE / HEMLOCK TWIGS AND NEEDLES.

E. SEED MIXES: SHALL MEET THE REQUIREMENTS OF MASSACHUSETTS HIGHWAY DEPARTMENT STANDARD SPECIFICATIONS FOR HIGHWAYS AND BRIDGES, LATEST EDITION SECTION 6.03.0 OR 6.03.1 AS APPROPRIATE.

F. EXCELSIOR BLANKET: CURLED WOOD FIBER ON PHOTODEGRADABLE EXTRUDED PLASTIC MATRIX, 80% OF FIBERS 6-INCHES LONG OR LONGER, WEIGHT 0.975 POUNDS / SY, CONTAINING NO CHEMICAL ADDITIVES. USE CURLEX I BLANKET BY AMERICAN EXCELSIOR COMPANY, OR APPROVED

G. ROCK RIPRAP: SOUND, ANGULAR, 6-INCH MINUS PROCESSED ROCK, BLAST ROCK, OR TAILINGS.

H. CRUSHED STONE: SOUND, ANGULAR, 2-INCH MINUS PROCESSED CRUSHED STONE.

PART 3 — EXECUTION

3.01 THROUGHOUT CONSTRUCTION

A. DEVISE WORK SEQUENCE SO AS TO LIMIT DRAINAGE AREA THAT IS TRIBUTARY TO DISTURBED AREAS. DEVISE, EMPLOY, AND MAINTAIN CONTROL MEASURES SUCH AS DIVERSION CHANNELS AND BERMS, STRATEGICALLY LOCATED STOCKPILES, AND SEDIMENT BASINS TO SUBDIVIDE DRAINAGE AREAS INTO SMALL, MANAGEABLE SUBAREAS, THEREBY MINIMIZING RUNOFF AND THE POTENTIAL FOR EROSION.

B. MAINTAIN BARRIER AT LIMIT OF WORK AND PROTECT EXISTING VEGETATION / FACILITIES OUTSIDE OF LIMIT OF WORK.

C. MAINTAIN SPARE MATERIAL STOCKPILES FOR IMMEDIATE EMPLOYMENT / REPAIR / EXPANSION OF CONTROL MEASURES. AT A MINIMUM, SUCH MATERIALS SHALL INCLUDE STRAW BALES, SILT FENCE AND STAKES, AND CRUSHED STONE.

D. INSPECT AND MAINTAIN EFFECTIVENESS OF CONTROL MEASURES BY REPAIRING AS NECESSARY TO ENSURE INTENDED FUNCTION; BY SUPPLEMENTING AS NECESSARY FOR ADEQUATE EXTENT; BY REMOVING TRAPPED PRODUCTS OF EROSION AS NECESSARY TO MAINTAIN EFFECTIVE TRAP VOLUME.

E. LIMIT EXTENT OF WORK AREA SO THAT ALL DISTURBED AREAS CAN BE STABILIZED WITH CONTROL MEASURES WITHIN A 24-HOUR PERIOD.

F. INSTALL CONTROL MEASURES AS SOON AS PRACTICABLE AFTER EACH MANAGEABLE PORTION OF EARTHWORK IS COMPLETE. EMPLOY TEMPORARY MEASURES AS NECESSARY TO STABILIZE DISTURBED AREAS, EVEN WHERE SUBSEQUENT CONSTRUCTION OPERATIONS MAY REQUIRE RE-DISTURBANCE.

G. WHEN INTENSE RAINFALL IS EXPECTED, CONSIDER, DEVISE, AND EMPLOY REINFORCING CONTROL MEASURES PRIOR TO THE RAINFALL EVENT TO MEET THE REQUIREMENTS DESCRIBED IN 1.01.A. IF NECESSARY, EMPLOY TEMPORARY CONTROL MEASURES ON MATERIAL STOCKPILES TO COUNTERACT POTENTIAL SEDIMENT TRANSPORT DURING INTENSE RAINFALL.

H. WHEN VEHICLE REFUELING IS REQUIRED ON SITE, CONDUCT REFUELING OPERATIONS OUTSIDE OF ENVIRONMENTALLY SENSITIVE AREAS. SPILL KITS SHALL BE AVAILABLE ON SITE FOR THE DURATION OF CONSTRUCTION.

I. PROPERLY DISPOSE OF DEBRIS, SOLID WASTE, TRASH, AND CONSTRUCTION WASTE / BYPRODUCTS OFF SITE.

J. SWEEP ON-SITE PAVED AREAS AND OFF-SITE STREETS AS NECESSARY TO PREVENT SILT AND DEBRIS ORIGINATING ON SITE FROM ENTERING CLOSED DRAINAGE SYSTEMS AND / OR ENVIRONMENTALLY SENSITIVE AREAS. WHEN NECESSARY UTILIZE WATER SPRAYING, SURFACE ROUGHENING AND/OR APPLY POLYMERS, SPRAY-ON TACKIFIERS, CHLORIDES AND BARRIERS FOR DUST CONTROL.

K. INSPECT EROSION CONTROLS DAILY THROUGHOUT CONSTRUCTION REPAIR DAMAGED CONTROLS IMMEDIATELY.

3.02 SITE PREPARATION AND ACCESS

A. WALK SITE AND IDENTIFY LOCATIONS OF LIMIT OF WORK AND ENVIRONMENTALLY SENSITIVE AREAS. ESTABLISH CONSTRUCTION STAGING AREA, LOCATED BEYOND ENVIRONMENTALLY SENSITIVE

B. INSTALL CONTROL MEASURES AS SHOWN ON THE DRAWINGS, INCLUDING THOSE DEFINING THE LIMIT OF WORK.

C. LIMIT VEHICULAR TRAFFIC TO AND FROM SITE TO MINIMIZE TRANSPORT OF SEDIMENT.

3.03 CLEARING, GRUBBING, AND STRIPPING

A. SCHEDULE GRUBBING AND STRIPPING TO OCCUR IMMEDIATELY PRIOR TO EARTH DISTURBANCE. DEPENDING ON SITE AREA, CONSIDER MULTIPLE GRUBBING PHASES, SEQUENCED TO TAKE ADVANTAGE OF THE EROSION PREVENTION POTENTIAL OF EXISTING VEGETATIVE COVER.

B. MINIMIZE THE AREA OF EXISTING VEGETATION REMOVED WHEREVER POSSIBLE. NO GREATER THAN FIVE (5) ACRES SHALL BE UNSTABLE AT ANY TIME.

C. LOCATE AND SIZE STOCKPILES TO MINIMIZE EROSION POTENTIAL, TAKING ADVANTAGE OF TERRAIN SLOPE AND ASPECT, WHERE APPROPRIATE.

D. PROTECT VEGETATION, INCLUDING ROOT SYSTEMS, BEYOND LIMIT OF CLEARING.

E. PROCESS TIMBER, STUMPS, SLASH, AND BRUSH SO AS TO PROTECT ENVIRONMENTALLY SENSITIVE AREAS AND INSTALLED CONTROL MEASURES. PROPERLY DISPOSE OF EXCESS OFF SITE. BURIAL OF STUMPS ON SITE IS PROHIBITED.

3.04 EXCAVATION FOR BUILDING FOUNDATIONS AND UTILITIES

A. DEVISE AND INSTALL CONTROL MEASURES ADEQUATE TO HANDLE DISCHARGES AND TRAP SEDIMENT FROM FOOTING SUMP AND WELL POINT PUMPS PRIOR TO EXCAVATION.

B. ARMOR SUMP PUMP DISCHARGE LOCATIONS TO PREVENT EROSION AT POINT OF DISCHARGE AND AREAS DOWNSTREAM.

C. IF FOUNDATION EXCAVATIONS GRADE TO DAYLIGHT ON THE LOW SIDE, DEVISE AND INSTALL CONTROL MEASURES TO HANDLE SURFACE AND GROUNDWATER FLOW FROM EXCAVATION LOW

D. STOCKPILE EXCAVATED MATERIALS TO BAFFLE OVERLAND RUNOFF, AVOIDING THE CREATION OF LENGTHY PATHS OF CONCENTRATED RUNOFF. STOCKPILE SLOPES SHALL NOT EXCEED 2:1.

E. BACKFILL UTILITY TRENCHES AS SOON AS PRACTICABLE TO PREVENT FLOODING, SLOUGHING, POTENTIAL OVERFLOW, AND REPETITIVE EARTH DISTURBANCE.

3.05 SITE GRADING

A. WHERE APPLICABLE, FOLLOW EXCAVATION AND FILL PRACTICES SHOWN ON DRAWINGS TO LOCALIZE AND MINIMIZE EROSION.

B. MONITOR SEDIMENT VOLUME IN TEMPORARY SEDIMENT BASINS AND AT DIVERSION BERMS AND CHECK DAMS. IN ALL AREAS EXCEPT THOSE THAT DO NOT PRESENT POTENTIAL PROBLEMS WITH REGARD TO FUTURE SOIL STABILITY, DRAINAGE, OR BEARING CAPACITY, REMOVE AND PROPERLY DISPOSE OF TRAPPED SEDIMENT BEFORE BRINGING SITE TO FINAL SUBGRADE.

C. EXPOSED SOILS SHALL BE PERMANENTLY STABILIZED WITHIN FIVE (5) BUSINESS DAYS OF COMPLETION OF CONSTRUCTION OF A GIVEN AREA. EXPOSED AREAS WHERE NO WORK HAS OCCURRED FOR FOURTEEN (14) DAYS SHALL BE TEMPORARILY STABILIZED WITH HYDROSEED OR OTHER APPROVED METHOD.

D. SLOPES STEEPER THAN 3:1 SHALL BE STABILIZED IMMEDIATELY AFTER COMPLETION.

3.06 LANDSCAPING

A. COMPLETE LANDSCAPING AS SOON AS POSSIBLE AFTER COMPLETION OF FINAL SUBGRADE.

B. IMMEDIATELY AFTER PLACEMENT OF TOPSOIL, STABILIZE WITH CONTROL MEASURES INCLUDING, BUT NOT NECESSARILY LIMITED TO, SEED MIX, MULCH, AND / OR BLANKET.

C. PERMANENT SEEDING MAY BE PERFORMED IN THE SPRING PRIOR TO JULY 1 AND IN BETWEEN AUGUST 1 AND OCTOBER 15. PERMANENT SEEDING AT OTHER TIMES SHALL BE APPROVED AND SHALL ONLY BE ALLOWED WITH AN APPROVED MULCHING AND IRRIGATION PROGRAM.

GENERAL SEQUENCE OF CONSTRUCTION

1. PLACE LIMIT OF WORK BARRIERS, FENCES, CONSTRUCTION ENTRANCES AND REQUIRED

FENCING & SIGNS. 2. CONSTRUCT SEDIMENT TRAPS & BARRIERS AND PLACE OTHER CONTROLS, DIVERSION

TRENCHES, PERIMETER DIKES, WATER BARS & OUTLET PROTECTION. ESTABLISH STOCKPILE AND STAGING AREAS.

4. CUT TREES AND SHRUBS AND REMOVE FROM SITE OR STOCKPILE AND PROTECT STOCKPILE(S) BY APPROVED METHODS.

5. EXCAVATE STUMPS AND REMOVE FROM SITE OR STOCKPILE AND PROTECT STOCKPILE(S) BY APPROVED METHODS.

COMMENCE CONSTRUCTION ON WETLAND CROSSING.

INSTALL DRAINAGE SYSTEM BEGINNING WITH INFILTRATION BASIN AREA. INSTALL, STABILIZE AND PROTECT INFILTRATION BASIN AREAS AND OTHER AREAS DISTURBED FOR COMPONENTS OF DRAINAGE SYSTEM (INFILTRATION BASIN IS TO REMAIN OFFLINE UNTIL ROADWAY CONSTRUCTION IS COMPLETE AND STABILIZED).

8. CLEAR, ROUGH GRADE & STABILIZE SLOPES OF ROADWAY. 9. BEGIN INSTALLATION OF OTHER UTILITIES. ESTABLISH COVER, STABILIZE AND PROTECT AREAS DISTURBED FOR UTILITY INSTALLATION.


10. BEGIN EXCAVATION FOR STRUCTURES. STOCKPILE AND PROTECT EXCAVATED MATERIALS. 11. BACKFILL FOUNDATIONS STABILIZE ALL DISTURBED AREAS AND REMOVE EXCESS SOIL FROM

12. PERFORM SITE WORK IN ACCORDANCE WITH "EROSION AND SEDIMENT CONTROL REQUIREMENTS, PART 3 - EXECUTION".


13. VERIFY ALL AREAS HAVE BEEN STABILIZED, RE-SEED EXPOSED SOILS. 14. CLEAN INFILTRATION AREA, CLEAN CATCH BASINS AND STORM DRAINS. REMOVE SOILS FROM


15. REMOVE ALL EROSION CONTROLS, LIMIT OF WORK BARRIERS, FENCES, CONSTRUCTION ENTRANCES, SIGNS AND SWEEP PAVED AREAS.


PART 3 - CONTINUED




EXCAVATION PROCEDURE










[2] WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. [3] WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

[4] USE SANDBAGS, STRAW BALES OR OTHER APPROVED METHODS TO CHANNELIZE RUNOFF

CONSTRUCTION ENTRANCE

TO BASIN AS REQUIRED.



CONSTRUCTION SAFETY FENCE



Andrews Survey & Engineering, Inc. Land Surveying - Civil Engineering - Site Planning

P.O. Box 312, 104 Mendon Street Uxbridge, Massachusetts 01569-0312 P: 508-278-3897 F: 508-278-2289

This drawing and the design are property of Andrews Survey & Engineering, Inc. and shall not be altered or reused in whole or part without the express written permission of Andrews Survey & Engineering, Inc. Copyright ©2014

APPROVAL UNDER SITE PLAN REVIEW. STOW PLANNING BOARD BEING A MAJORITY DATE:

APPROVAL UNDER SITE PLAN REVIEW. HUDSON PLANNING BOARD

BEING A MAJORITY DATE:


NO N 0 8 7 0 LLI EV 0 OLI DE' 17] TOV $\sum_{i=1}^{n} a_i \mathbf{r}_i$

REVISIONS DATE DESCRIPTION 4/22/1 PER REVIEW COMMENTS PER REVIEW COMMENTS

..\dwg\2014-021 $_{SP}-$ R6.dwg DRAWN BY TRB, SJO CHECKED BY JANUARY 20, 2015 PROJECT NO. | 2014-021


SHEET TITLE

EROSION & SEDIMENT CONTROL NOTES SHEET 3 OF 4





C - 3.3


DRAWING NO.











This drawing and the design are property of Andrews Survey & Engineering, Inc. and shall not be altered or reused in whole or part without the express written permission of Andrews Survey & Engineering, Inc.

Copyright ©2014

APPROVAL UNDER SITE PLAN REVIEW.

STOW PLANNING BOARD

BEING A MAJORITY DATE:

APPROVAL UNDER SITE PLAN REVIEW. HUDSON PLANNING BOARD

BEING A MAJORITY

THE COLLINGS FOUNDATION
SITE DEVELOPMENT PLAN
137 BARTON ROAD
STOW, MA 01775


COLLINGS FOUNDATION, INC.
P.O. BOX 248
STOW, MA 01775


REVISIONS								
NO.	DATE	DESCRIPTION						
1	4/22/15	PER REVIEW COMMENTS						
2	5/18/15	PER REVIEW COMMENTS						
CAD	FILE	\dwg\2014-021_SP-R6.dwg						
DRAWN BY		TRB, SJO						
CHEC	KED BY	РВН						
DATE	•	JANUARY 20, 2015						
PROJ	ECT NO.	2014-021						
	<u> </u>							

SHEET TITLE

EROSION & SEDIMENT CONTROL NOTES

SHEET 4 OF 4





WETLAND MITIGATION CONSTRUCTION PROTOCOL:

- 1. THE FOLLOWING PROTOCOL CONFORMS TO THE GENERAL PERFORMANCE STANDARDS IN THE MA WETLANDS PROTECTION ACT REGULATIONS AT 310 CMR 10.55(4)(B) AS SUMMARIZED IN TABLE 2. PLEASE NOTE THAT THE MITIGATION AREA WILL BE BROUGHT TO SUB—GRADE PRIOR TO INITIATING WORK AT THE WETLAND CROSSING.
- 2. THE WETLAND BOUNDARIES (I.E., DOWN GRADIENT EDGES OF THE WETLAND MITIGATION AREA) WILL BE MARKED IN THE FIELD.
- 3. PRIOR TO THE START OF EARTH—MOVING ACTIVITIES IN THE MITIGATION AREA, AN EROSION CONTROL BARRIER OF PROPERLY INSTALLED SILTATION FENCE (I.E., THE BOTTOM FEW INCHES OF THE SILTATION FENCE INSTALLED IN A NARROW, TRENCH AND THE TRENCH FILLED WITH SOIL AROUND THE SILTATION FENCE) WILL BE INSTALLED ALONG THE WETLAND BOUNDARIES BETWEEN THE WETLAND AND THE WETLAND MITIGATION AREA. THE WETLAND MITIGATION AREA WILL THEN BE CLEARED AND GRUBBED, WITH THE EXCEPTION OF THE TREES THAT HAVE BEEN MARKED TO BE SAVED.
- 4. THE PROPOSED FINAL GRADE FOR THE MITIGATION AREA SHOULD APPROXIMATE THE ELEVATION OF THE ADJACENT WETLAND AREAS, AS NOTED ON THE SITE PLANS. THE MITIGATION AREA WILL BE EXCAVATED TO A DEPTH OF 12 INCHES BELOW THE PROPOSED FINAL GRADE. THE EXCAVATION AND PLANTING WORK WILL BE CLOSELY SUPERVISED BY A QUALIFIED WETLAND SCIENTIST. MINOR MODIFICATIONS TO THE PROPOSED GRADING MAY BE MADE IN THE FIELD BY THE WETLAND SCIENTIST IN RESPONSE TO OBSERVED SUBSURFACE HYDROLOGIC CONDITIONS. ALL EXCAVATED MATERIAL WILL BE DISPOSED OF AWAY FROM ALL WETLAND RESOURCE AREAS. EIGHT TO TEN BOULDERS (1 TO 2 FOOT DIAMETER) WILL BE PLACED IN TWO PILES, AT SUBGRADE, WITHIN THE MITIGATION AREA TO PROVIDE WILDLIFE SHELTERS. TWO TREE TRUNKS, APPROXIMATELY 20 FEET IN LENGTH, WILL BE "PLANTED" UPRIGHT, WITHIN THE MITIGATION AREA, TO PROVIDE NESTING CAVITIES AND FORAGE OPPORTUNITIES.
- 5. EXISTING TOPSOILS WITHIN THE IMPACT AREA WILL BE EXCAVATED, STOCKPILED AND KEPT MOIST BY WATERING AND/OR COVERING.
- 6. RELOCATED WETLAND TOPSOILS WILL BE SUPPLEMENTED WITH A 1:1 MIXTURE OF HIGH QUALITY, LOAMY TOPSOIL AND LEAF MOLD COMPOST, AS NECESSARY, TO APPROXIMATE 12 INCHES IN THICKNESS THROUGHOUT THE MITIGATION AREA. THE SUBSTRATE WILL BE ROUGHLY GRADED TO PROVIDE AN APPROPRIATE MICROTOPOGRAPHY. A MINIMUM OF 4 INCHES OF LOAMY TOPSOIL WILL BE APPLIED TO THE SIDE—SLOPES OF THE WETLAND MITIGATION AREA. THE SIDE SLOPES SHOULD BE STABILIZED AS NECESSARY TO PREVENT EROSION.
- 7. WILDLIFE ENHANCEMENT MEASURES INCLUDING THREE TREE TRUNKS AND ONE ROCK PILE WILL BE INSTALLED WITHIN EACH MITIGATION AREA. THE TREE TRUNKS WILL CONSIST OF 15 TO 20 FOOT LOGS PLACED RANDOMLY ON THE FINISHED SURFACE. THE TREE TRUNKS WILL PROVIDE FOOD, FORAGE AND CAVITY NESTING OPPORTUNITIES. THE ROCK PILES WILL CONSIST OF FOUR OR FIVE BOULDER EACH (APPROXIMATELY 24 INCHES IN DIAMETER) PILED AT SUB-GRADES SO AS TO CREATE CREVICES AND CAVITIES FOR SHELTER AND NESTING.
- 8. AN EROSION CONTROL BARRIER COMPRISING ONLY TOED—IN SILTATION FENCE WILL BE PROPERLY INSTALLED BETWEEN THE COMPLETED MITIGATION AREA AND THE ADJACENT UPLAND SIDESLOPES.
- 9. PLANTING WILL BE DONE ONLY DURING THE BEGINNING (APRIL 15 THROUGH JUNE) OR END (SEPTEMBER 1 TO NOVEMBER 15) OF THE GROWING SEASON. PLANTING IN THE MID—GROWING SEASON IS ONLY ACCEPTABLE IF IRRIGATION IS PROVIDED. THE PLANT SPECIES IDENTIFIED IN THE TABLE BELOW WILL BE PLANTED IN THE MITIGATION AREA EITHER BY TRANSPLANT OR FROM NURSERY STOCK. THE SAPLINGS WILL BE DISTRIBUTED THROUGHOUT THE AREA. THE SHRUBS WILL BE PLANTED RANDOMLY THROUGHOUT THE AREA WITH THE AVERAGE SPACING BETWEEN SHRUBS APPROXIMATELY 5 FEET ON—CENTER. THE WOODY VEGETATION SHOULD NOT BE PLANTED IN ROWS. THE FERNS WILL BE PLANTED BETWEEN THE SHRUBS AND SAPLINGS.
- 10. THE MITIGATION AREA WILL BE SEEDED WITH "NEW ENGLAND WETMIX" AS PER NEW ENGLAND WETLAND PLANTS, INC SPECIFICATIONS OR APPROVED EQUAL TO PROVIDE FOR TEMPORARY EROSION CONTROL AND MOISTURE RETENTION.
- 11. THE MITIGATION AREAS WILL BE INSPECTED, BY A QUALIFIED WETLAND SCIENTIST, AT THE END OF EACH GROWING SEASON FOR A MINIMUM OF TWO YEARS OR UNTIL SUCH TIME AS THE REQUIRED 75% OF VEGETATIVE COVER WITH WETLAND SPECIES HAS BEEN ESTABLISHED. WRITTEN RESULTS OF THESE INSPECTIONS WILL BE SUBMITTED TO THE CONSERVATION COMMISSION.
- 12. AFTER THE WETLAND MITIGATION AREA HAS BECOME VEGETATIVELY STABILIZED, AND FOLLOWING APPROVAL OF THE ISSUING AUTHORITY, THE SILTATION FENCE AND ALL WOODEN STAKES WILL BE REMOVED AND DISPOSED OF PROPERLY.

SEQUENCE OF CONSTRUCTION:

ALL DRAINAGE STRUCTURES INCLUDING DETENTION PONDS, CROSS CULVERTS, STORM WATER MANHOLES, CATCH BASINS, AND ALL OTHER UNDERGROUND UTILITIES SHALL BE CONSTRUCTED AND STABILIZED PRIOR TO ANY LOT DEVELOPMENT. IMMEDIATELY FOLLOWING CATCH BASIN INSTALLATION, HAY BALES SHALL BE PLACED AROUND RIMS AND ALL DISTURBED AREAS SHALL BE HYDROSEEDED, MULCHED OR COVERED WITH ENVIRONMENTAL MATTING AND CHECKED REGULARLY TO PREVENT EROSION FROM TAKING PLACE.



WETLANDS FILL AREA

MITIGATION AREA

TOTAL WETLAND FILL AREA FROM ROAD CROSSING: 436 SQ. FT. \pm TOTAL MITIGATION AREA: 1,248 SQ. FT. \pm

GENERAL NOTES:


PRIOR TO CONSTRUCTION AND INSTALLATION OF THE PROPOSED DRAINAGE PIPES AND RETAINING WALLS SEPARATE APPROVALS AND/OR PERMITS SHALL BE OBTAINED FROM THE FOLLOWING; INCLUDING BUT NOT LIMITED TO THE TOWN OF STOW CONSERVATION COMMISSION, DEPARTMENT OF PUBLIC WORKS, INSPECTOR OF BUILDINGS, TOWN OF STOW PLANNING BOARD AND CONSULTING ENGINEER(S).

TABLE 1.


_			
	PUBLIC INTERESTS:	VALUE OF AREAS TO BE ALTERED:	VALUE OF MITIGATION AREAS:
	PUBLIC AND PRIVATE WATER SUPPLY, GROUNDWATER SUPPLY	YES. RECHARGES GROUNDWATER THROUGH INFILTRATION. SEASONALLY RECHARGES SURFACE WATER THROUGH OVERLAND FLOW. OVERLAND FLOW WILL BE MAINTAINED THROUGH CULVERTS.	YES. WILL ALSO RECHARGE GROUNDWATER THROUGH INFILTRATION IN FRIABLE SUBSOIL AND SUBSTRATE.
	FLOOD CONTROL AND STORM DAMAGE PREVENTION	YES. SOME STORAGE OF RUNOFF IN SEASONALLY SATURATED SOILS	YES SEASONALLY SATURATED SOILS WILL STORE EQUAL OR GREATER VOLUMES OF RUNOFF.
	PREVENTION OF POLLUTION	YES. CONTAMINANTS AND EXCESS NUTRIENTS RETAINED IN, AND DEGRADED BY, MINERAL AND ORGANIC COMPONENTS OF HYDRIC SOILS.	YES. CONTAMINANTS AND EXCESS NUTRIENTS RETAINED IN, AND DEGRADED BY, MINERAL AND ORGANIC COMPONENTS OF HYDRIC SOILS.
	FISHERIES	N/A. NO PERENNIAL WATERWAY OR WATERBODY	N/A. NO PERENNIAL WATERWAY OR WATERBODY
	WILDLIFE HABITAT	YES, EXISTING VEGETATIVE LAYERS, SOIL STRUCTURE, DEADWOOD AND SURFACE STONES PROVIDE FORAGING AND SHELTER OPPORTUNITIES.	YES. REPLICATED SOIL STRUCTURE, PLANTING, BOULDER PLACEMENT AND TREE SNAGS WILL PROVIDE OPPORTUNITIES FOR WILDLIFE SHELTER AND FORAGE.


TABLE 2.

PERFORMANCE STANDARD:	STANDARDS MET WITHIN MITIGATION AREA:				
EQUAL SURFACE AREAS (800 S.F. ALTERED).	YES. GREATER SURFACE AREA (1,248 S.F. MITIGATED)				
SIMILAR GROUNDWATER AND SURFACE ELEVATIONS.	YES SIMILAR ELEVATIONS.				
LOCATION RELATIVE TO BANK	YES. SIMILAR PROXIMITY TO STREAM BANK				
UNRESTRICTED HYDRAULIC CONNECTION.	YES. UNRESTRICTED CONNECTION TO SAME BORDERING WETLAND				
SAME GENERAL LOCATION.	YES. AS CLOSE AS POSSIBLE TO IMPACTED WETLAND				
MINIMUM 75% COVER OF NATIVE WETLAND PLANTS WITHIN TWO GROWING SEASONS AND PREVENTION OF SOIL EROSION.	YES. TO BE INSURED BY FOLLOWING CONSTRUCTION AND PLANTING PROTOCOL COMBINED WITH ANNUAL MONITORING AND RE-PLANTING AND/OR MODIFICATION AS NECESSARY. PLANTING DESIGNED TO REPLICATE LOST AREA(S) IN-KIND. EROSION PREVENTED WITH SILTATION BARRIERS.				
CULVERT OPENNESS RATIO OF ≥ 0.25 (ALL CALCULATIONS DONE IN METERS)	YES. OPENNESS RATIO = 0.91 X—SEC CULVERT AREA PRE—EMBED — EMBEDDED AREA CULVERT LENGTH				
	$\frac{8.6(M^2) - 1.7(M^2)}{7.62 (M) = 25.0 \text{ FT}} = 0.91$				




CROSS SECTION
A-A






2 RETAINING WALL WITH PIPE OUTLETS





TYPICAL WETLAND MITIGATION DETAILS



CROSS SECTION



Andrews Survey & Engineering, Inc.
Land Surveying - Civil Engineering - Site Planning

P.O. Box 312, 104 Mendon Street Uxbridge, Massachusetts 01569-0312 P: 508-278-3897 F: 508-278-2289

This drawing and the design are property of Andrews Survey & Engineering, Inc. and shall not be altered or reused in whole or part without the express written permission of Andrews Survey & Engineering, Inc.

Copyright ©2014

APPROVAL UNDER SITE PLAN REVIEW.
STOW PLANNING BOARD

BEING A MAJORITY DATE:

HUDSON PLANNING BOARD

APPROVAL UNDER SITE PLAN REVIEW.

DEING A MAIO

BEING A MAJORITY

COLLINGS FOUNDATION

DEVELOPMENT PLAN

137 BARTON ROAD

STOW, MA 01775

NGS FOUNDATION, INC.

P.0. TOW

OL

DATE:

REVISIONS

O. DATE DESCRIPTION

1 4/22/15 PER REVIEW COMMENTS

2 5/18/15 PER REVIEW COMMENTS

CAD FILE ...\dwg\2014-021_SP-R6.dwg

DRAWN BY TRB, SJO


CHECKED BY PBH

DATE JANUARY 20, 2015

PROJECT NO. 2014-021


SHEET TITLE


WETLAND CROSSING & MITIGATION PLAN





C-4.2


DRAWING NO.















- VEGETATION COVER TO BE "NEW ENGLAND





SCALE: N.T.S.







Andrews Survey & Engineering, Inc. Land Surveying - Civil Engineering - Site Planning

P.O. Box 312, 104 Mendon Street Uxbridge, Massachusetts 01569-0312 P: 508-278-3897 F: 508-278-2289

This drawing and the design are property of Andrews Survey & Engineering, Inc. and shall not be altered or reused in whole or part without the express written permission of Andrews Survey & Engineering, Inc. Copyright ©2014

APPROVAL UNDER SITE PLAN REVIEW. STOW PLANNING BOARD BEING A MAJORITY

APPROVAL UNDER SITE PLAN REVIEW. HUDSON PLANNING BOARD

BEING A MAJORITY

FOUNDATION MENT PLAN ON ROAD NO 1775 248 0177 COLLING DEVEI GS F.O. P.O. TOW, 田二 COLLI

REVISIONS NO. DATE DESCRIPTION 1 4/22/15 PER REVIEW COMMENTS 2 | 5/18/15 PER REVIEW COMMENTS CAD FILE .\dwg\2014-021_SP-R6.dwg DRAWN BY TRB, SJO CHECKED BY JANUARY 20, 2015 PROJECT NO. | 2014-021


SHEET TITLE


CONSTRUCTION **DETAILS**

SHEET 2 OF 3





DRAWING NO. C - 6.2PLAN NO. L-4403








1) CULTEC RECHARGER 330 XL HD CHAMBER











248 0177


PROJECT:		THE COI SITE DI	137 BA STOW.		APPLICANT:	COLLINGS F P.O. STOW,
	REVISIONS					
NC).	DATE		DESCRIPTION		
1	4	1/22/15	PER REVIEW COMMENTS			
2		5/18/15		PER	RE	VIEW COMMENTS
СА	DF	ILE	\dwg\2014-021_SP-R6.dwg TRB, SJO PBH JANUARY 20, 2015 2014-021			
DR	/WA	I BY				
СН	ECK	ED BY				
DA						
PR	OJE	CT NO.				
	SHEET					

NGS FOI ELOPMEN ARTON 1

DETAILS FOR FULL SITE BUILD-OUT


CONSTRUCTION


SHEET 2 OF 3




C-6.3

DRAWING NO.









GENERAL NOTES FOR LOAM BORROW:

- 1) SCOPE OF WORK: FOR THIS PROJECT, THE WORK SHALL INCLUDE PLACING LOAM IN AREAS DENUDED BY CONSTRUCTION.
- 2) THE CONTRACTOR SHALL FURNISH A CERTIFIED LABORATORY REPORT SHOWING THE SOILS CLASSIFICATION AND NUTRIENT ANALYSIS OF REPRESENTATIVE SAMPLES OF THE LOAM THIS IS PROPOSED TO BE USED, INCLUDING THE EXTENT OF LIME AND FERTILIZER REQUIRED. ALL COSTS FOR SUCH WORK SHALL BE BORNE BY THE CONTRACTOR.
- 3) IN ACCORDANCE WITH THE SPECIFIC REQUIREMENTS OF THIS PROJECT, EXISTING ON-SITE SOIL MAY BE RE-USED AS LOAM BORROW ONLY IF IT MEETS THIS SPECIFICATION. EXISTING TOPSOIL THAT DOES NOT MEET THIS SPECIFICATION MAY BE RE-USED ONLY UP TO THE SUBGRADE ELEVATION WITHIN THE LIMITS OF AREAS TO RECEIVE NEW LOAM BORROW. THE CONTRACTOR SHALL FURNISH ALL REQUIRED LOAM BORROW. FROM OFF-SITE SOURCES. AS NECESSARY. TO COMPLETE THE PROJECT.
- 4) SCREENED LOAM SHALL BE "FINE SANDY LOAM" OR "SANDY LOAM" DETERMINED BY MECHANICAL ANALYSIS (ASTM D-422) AND BASED ON THE "USDA CLASSIFICATION SYSTEM". SCREENED LOAM SHALL HAVE THE FOLLOWING MECHANICAL ANALYSIS:

TEXTURAL CLASS PERCENTAGE	PERCENTAGE OF TOTAL WEIGHT	AVERAGE PERCENTAGE
SAND (0.05 - 2.0 MM)	45 - 75	60
SILT (0.002 - 0.05 MM)	5 - 35	25
CLAY (LESS THAN 0.002 MM)	5 – 20	15

- 4) SCREENED LOAM SHALL BE A NATURAL PRODUCT CONSISTING PRIMARILY OF NATURAL TOPSOIL, FREE FROM SUBSOIL, AND OBTAINED FROM AN AREA THAT HAS NEVER BEEN STRIPPED BEFORE. SCREENED LOAM SHALL NOT CONTAIN LESS THAN FIVE PERCENT (5%) NOR MORE THAN TEN PERCENT (10%) ORGANIC MATTER. TO ADJUST ORGANIC MATTER CONTENT, THE SOIL MAY BE AMENDED, PRIOR TO SITE DELIVERY, BY THE ADDITION OF COMPOSTED LEAF MOLD OR PEAT MOSS. NO MIXING OR AMENDING OF LOAM IS PERMITTED ON SITE.
- 5) THE LOAM SHALL NOT BE DELIVERED IN A WET OR FROZEN CONDITION.
- 6) SCREENED LOAM SHALL CONSIST OF FERTILE. FRIABLE





GENERAL NOTES FOR TURFGRASS SEEDING:

1) SCOPE OF WORK: FOR THIS PROJECT, THE WORK SHALL INCLUDE SEEDING AREAS DENUDED BY CONSTRUCTION.

2) ALL AREAS SHALL BE SEEDED WITHIN 30 DAYS AFTER FINISHED GRADES ARE ESTABLISHED AND OTHER ELEMENTS INCLUDED IN THIS CONTRACT ARE CONSTRUCTED.

3) SEED SPECIFICATIONS:

A) A) AREAS RECEIVING FULL SUN OR PART SHADE:

FESCUE/BLUEGRASS/PERENNIAL RYEGRASS MIXTURE: MIXTURE REQUIREMENTS ARE AS FOLLOWS (WITH APPROXIMATE PERCENTAGES):

35% FINE FESCUE (ENDOPHYTIC) 35% KENTUCKY BLUEGRASS 30% PERENNIAL RYEGRASS (ENDOPHYTIC)

B) AREAS RECEIVING MOSTLY SHADE:

FESCUE/PERENNIAL RYEGRASS MIXTURE: MIXTURE REQUIREMENTS ARE AS FOLLOWS (WITH APPROXIMATE PERCENTAGES):

90% FINE FESCUE (ENDOPHYTIC) 10% PERENNIAL RYEGRASS (ENDOPHYTIC)

C) ANY PROPOSED SUBSTITUTIONS SHALL BE PRESENTED TO THE LANDSCAPE ARCHITECT FOR APPROVAL PRIOR TO SEEDING.

D) ALL SEED SHALL HAVE A MINIMUM PURITY OF 98 PERCENT AND A GERMINATION RATE OF 85 PERCENT.

E) ALL SEED SHALL BE LABELED TO SHOW THAT IT IS WITHIN THE REQUIREMENTS OF THE USDA AS TO PURITY, GERMINATION. AND PRESENCE OF RESTRICTED OR PROHIBITED WEEDS.

4) <u>BED PREPARATION FOR AREAS TO BE SEEDED:</u> A ROTOVATOR, CHISEL PLOW, OR CULTIVATOR SHALL BE USED TO WORK THE SOIL TO A DEPTH OF SIX INCHES. AFTER THIS OPERATION, REMOVE AND DISPOSE OF STICKS, STONES OVER 1 INCH DIAMETER, AND RUBBISH TO A MINIMUM DEPTH OF TWO INCHES.

5) LIME AND NUTRIENTS: LIME SHALL BE GROUND DOLOMITIC LIMESTONE, APPLIED AT THE RATE OF 50 POUNDS PER 1000 SQUARE FEET. LIME SHALL BE WELL-MIXED INTO THE TOP THREE INCHES OF LOAM.

6) FERTILIZER: FERTILIZER SHALL BE A COMMERCIAL GRADE WITH A MINIMUM OF 50 PERCENT OF THE NITROGEN COMPONENT IN A CONTROLLED RELEASE FORM LABELED TO RELEASE NITROGEN FOR A MINIMUM OF SIX WEEKS. FERTILIZER SHALL HAVE AN N/P/K RATIO IN THE RANGE OF 1:1:1 TO 1:2:2. IT SHALL BE APPLIED AT A RATE WHICH ACHIEVES ONE POUND OF NITROGEN PER 1000 SQUARE FEET.

7) SEEDING PROCEDURE: SOWING OF SEED SHALL BE DONE ONLY AFTER THE PREPARED SOIL, TO WHICH LIME AND FERTILIZER HAVE BEEN ADDED AS SPECIFIED. HAS BEEN THOROUGHLY SETTLED BY RAINFALL OR ARTIFICIAL WATERING. IMMEDIATELY BEFORE ANY SEED IS SOWN. THE GROUND SHALL BE SCARIFIED AS SPECIFIED. LAWN AREAS SHALL BE SEEDED EVENLY WITH A MECHANICAL SPREADER. SEED MIXTURES SHALL BE SOWN AT A RATE OF 5 POUNDS PER 1000 SQUARE FEET. AFTER SEEDING. THE LAWN SHALL BE LIGHTLY RAKED, ROLLED WITH A 200-POUND ROLLER, AND WATERED WITH A FINE SPRAY. THIS METHOD OF SEEDING MAY BE VARIED AT THE DISCRETION OF THE CONTRACTOR ON HIS OWN RESPONSIBILITY TO ESTABLISH A SMOOTH. UNIFORMLY GRASSED LAWN.


8) SEED FOR PERMANENT TURFGRASS SHALL ONLY BE SOWN FROM THE THIRD WEEK IN APRIL THROUGH JUNE AND DURING THE MONTH OF SEPTEMBER.

9) TEMPORARY SEEDING FOR EROSION CONTROL: IN THE EVENT THAT THE CONTRACT IS SUSPENDED. TEMPORARY SEEDING SHALL BE USED ON ANY BARE AREAS THAT MAY BE SUBJECT TO EROSION AND WHERE TEMPORARY VEGETATION CAN BE USED TO RETARD EROSION FROM 2 TO 12 MONTHS. THE SEED TYPE USED FOR TEMPORARY COVER SHALL BE 100 PERCENT TALL FESCUE APPLIED AT A RATE OF 300 POUNDS PER ACRE.

10) MAINTENANCE: MAINTAIN THE TURFGRASS FROM TIME OF INSTALLATION UNTIL THE FINAL INSPECTION IMMEDIATELY PRIOR TO THE BEGINNING OF THE GUARANTEE PERIOD. MAINTENANCE SHALL INCLUDE WATERING OF TURE AREAS. REPAIRS TO TURE AREAS. AND OTHER NECESSARY OPERATIONS. THE MAINTAINED TURE AREAS SHALL BE MOWED TO A UNIFORM HEIGHT OF APPROXIMATELY TWO AND ONE-HALF INCHES. MOWING SHALL BE PROVIDED AS REQUIRED SO THAT THE TURF NEVER EXCEEDS FOUR INCHES IN HEIGHT, TURE SHALL BE PROTECTED AND REPLANTED AS NECESSARY TO ESTABLISH A UNIFORM STAND OF THE SPECIFIED TURF AND UNTIL ACCEPTANCE. SCATTERED BARE SPOTS, NONE OF WHICH IS LARGER THAN ONE SQUARE FOOT, WILL BE ALLOWED UP TO A MAXIMUM OF THREE PERCENT OF ANY TURF AREA. WHEN TURF AREAS ARE READY FOR FINAL INSPECTION. THE MAINTAINED TURF AREAS SHALL BE NEATLY MOWED TO THE UNIFORM HEIGHTS AS NOTED ABOVE. THE LAWNS SHALL BE CONSIDERED ESTABLISHED ONLY WHEN THE SPECIFIED GRASS IS VIGOROUS AND GROWING WELL IN ADDITION TO MEETING THE OTHER REQUIREMENTS SPECIFIED. AT THE TIME OF ACCEPTANCE FOLLOWING FINAL INSPECTION. THE CONTRACTOR IS RELIEVED OF ROUTINE MAINTENANCE RESPONSIBILITIES FOR THE TURF UNDER THIS CONTRACT.

11) FINAL INSPECTION, CLEANUP AND COMPLETION: FINAL INSPECTION SHALL BE FOR THE COMPLETED LANDSCAPE AND SHALL BE MADE AT THE CONCLUSION OF THE LANDSCAPE WORK. UPON COMPLETION OF THE WORK, THE CONTRACTOR SHALL REMOVE FROM THE SITE ALL EQUIPMENT AND OTHER ARTICLES USED. ALL EXCESS SOIL, STONES, AND DEBRIS SHALL BE REMOVED FROM THE SITE. ALL WORK AREAS SHALL BE LEFT IN A CLEAN AND NEAT CONDITION. ALL DAMAGE TO EXISTING CONSTRUCTION CAUSED BY THE LANDSCAPING OPERATIONS SHALL BE REPAIRED TO THE SATISFACTION OF THE OWNER AT THE CONTRACTOR'S

12) GUARANTY AND REPLACEMENT: IF A SATISFACTORY STAND OF MAINTAINED TURF HAS BEEN PRODUCED AT THE TIME OF FINAL INSPECTION. IT SHALL BE GUARANTEED THROUGH ONE COMPLETE GROWING SEASON. IF RENOVATION AND/OR RESEEDING ARE REQUIRED AT THE END OF THE GUARANTEE PERIOD. THIS WORK SHALL BE DONE IN CONFORMANCE WITH THE REQUIREMENTS NOTED ABOVE. IF A SATISFACTORY STAND OF MAINTAINED TURF HAS NOT BEEN PRODUCED AT THE TIME OF FINAL INSPECTION, NECESSARY REPAIRS SHALL BE PERFORMED IN CONFORMANCE WITH THE REQUIREMENTS NOTED ABOVE. UPON COMPLETION OF THESE REPAIRS. THE TURF GRASS SHALL BE GUARANTEED AS NOTED ABOVE.





GENERAL NOTES FOR TREE, SHRUB, AND GROUNDCOVER PLANTINGS:

1) NOMENCLATURE: THE NAMES OF PLANTS REQUIRED UNDER THIS CONTRACT SHALL CONFORM TO THOSE GIVEN IN STANDARDIZED PLANT NAMES, 1942 EDITION, PREPARED BY THE AMERICAN JOINT COMMITTEE ON HORTICULTURAL NOMENCLATURE. NAMES OF VARIETIES NOT INCLUDED THEREIN SHALL CONFORM GENERALLY WITH NAMES ACCEPTED IN THE NURSERY TRADE.

2) QUALITY AND SIZE: PLANTS SHALL HAVE A HABIT OF GROWTH THAT IS NORMAL FOR THE SPECIES AND SHALL BE SOUND, HEALTHY, VIGOROUS, AND FREE FROM INSECT PESTS, PLANT DISEASES, AND INJURIES. ALL PLANTS SHALL EQUAL OR EXCEED THE MEASUREMENTS SPECIFIED IN THE PLANT LIST, WHICH ARE MINIMUM ACCEPTABLE SIZES. THEY SHALL BE MEASURED BEFORE PRUNING IS DONE AT TIME OF PLANTING. REQUIREMENTS FOR THE MEASUREMENTS, BRANCHING, GRADING, QUALITY, BALLING, AND BURLAPPING OF PLANTS IN THE PLANT LIST SHALL FOLLOW THE CODE OF STANDARDS CURRENTLY RECOMMENDED BY THE AMERICAN ASSOCIATIONS OF NURSERYMEN, INC., IN THE AMERICAN STANDARD FOR NURSERY STOCK.

3) SUBSTITUTIONS: SUBSTITUTIONS WILL BE PERMITTED ONLY UPON SUBMISSION OF PROOF THAT ANY PLANT AS SPECIFIED IS NOT OBTAINABLE DURING THE SCHEDULED PLANTING SEASON. WRITTEN AUTHORIZATION BY THE LANDSCAPE ARCHITECT SHALL BE REQUIRED FOR ANY SUBSTITUTION. THE NEAREST EQUIVALENT SIZE OR VARIETY OF PLANT HAVING THE SAME ESSENTIAL CHARACTERISTICS SHALL BE USED.

4) BALLED AND BURLAPPED MATERIALS: PLANTS DESIGNATED "B&B" IN THE PLANT LIST SHALL BE BALLED AND BURLAPPED. THEY SHALL BE DUG WITH FIRM, NATURAL BALLS OF EARTH OF SUFFICIENT DIAMETER AND DEPTH TO ENCOMPASS THE FIBROUS AND FEEDING ROOT SYSTEM NECESSARY FOR FULL RECOVERY OF THE PLANT. MATERIAL SHALL BE IN A CONDITION WHERE THE NATURAL ROOT COLLAR OF THE PLANT IS WITHIN APPROXIMATELY TWO (2) INCHES OF THE SOIL LEVEL OF THE BALL. BALLS SHALL BE FIRMLY WRAPPED WITH BURLAP OR SIMILAR MATERIAL AND BOUND WITH TWINE, CORD, OR WIRE MESH. NO SYNTHETIC FABRIC IS ALLOWED. WHERE NECESSARY TO PREVENT BREAKING OR CRACKING OF THE BALL DURING THE PROCESS OF PLANTING, THE BALL MAY BE SECURED TO A PLATFORM, BALLS SHALL BE KEPT MOIST AND SHADED UNTIL THEY ARE PLANTED. REMOVE ALL BALL TIES OR STRAPPING FROM ROOT BALL PRIOR TO PLANTING. PLANT IN ACCORDANCE WITH TREE AND SHRUB PLANTING DETAILS.

5) CONTAINER-GROWN MATERIALS: PLANTS NOT DESIGNATED OTHERWISE IN THE PLANT LIST MAY BE PURCHASED AS CONTAINER-GROWN OR BALLED/BURLAPPED CONTAINER-GROWN PLANTS. IF STORED ON THE SITE. SHALL BE WATERED THOROUGHLY AT LEAST ONCE EVERY 48 HOURS. ROOT SYSTEMS OF CONTAINER-GROWN PLANTS SHALL BE WELL-DEVELOPED BUT NOT IN "POT-BOUND" CONDITION OF DENSE, ENCIRCLING ROOTS. THE ROOT BALL OF THE PLANT SHALL BE LOOSENED TO ALLEVIATE ENCIRCLING ROOTS AND TO PROVIDE AN INCREASED ROOT INTERFACE WITH THE FILL SOIL. PLANT IN ACCORDANCE WITH TREE, SHRUB, AND GROUNDCOVER PLANTING DETAILS.

6) PROTECTION OF PLANTS PRIOR TO INSTALLATION: THE ROOT ZONE OF ALL PLANTS NOT YET INSTALLED SHALL BE PROTECTED FROM FREEZING, DRYING, AND DIRECT SUNLIGHT.

7) MULCHING: DOUBLE-SHREDDED HARDWOOD MULCH SHALL BE USED AS THE MULCH FOR ALL PLANT BEDS INDICATED ON THE LANDSCAPE PLAN, INCLUDING AREAS SURROUNDING THE PLANTS AS SHOWN ON THE TREE, SHRUB, AND GROUNDCOVER PLANTING DETAILS.

8) PLANTING SEASON: THE NORMAL PLANTING SEASON IS APRIL THROUGH NOVEMBER. SOME PLANTS SPECIFIED AS BALLED AND BURLAPPED CANNOT BE DUG DURING PORTIONS OF THIS PLANTING SEASON -- CHECK WITH NURSERIES FOR SPECIFICS. PLANTING OPERATIONS SHALL BE CONDUCTED UNDER FAVORABLE WEATHER CONDITIONS DURING THE NORMAL PLANTING SEASON.

9) WEATHER CONDITIONS: PLANTING SHALL NOT TAKE PLACE WHEN SOILS ON SITE ARE FROZEN OR WET AND IN POOR TILTH.

10) LAYOUT: NEW PLANTINGS SHALL BE LOCATED ACCORDING TO THE LANDSCAPE PLAN. THE CONTRACTOR SHALL STAKE THE PLANT LOCATIONS, AND SHALL THEN CONTACT THE LANDSCAPE ARCHITECT FOR APPROVAL

11) SETTING PLANTS: ALL PLANTS SHALL BE PLANTED IN PREPARED SOILS BEDS, AND SET ON FIRM SOIL TO SUCH DEPTH AS INDICATED IN THE PLANTING DETAILS. TREES, SHRUBS, GROUNDCOVERS, AND PERENNIALS SHALL BE SET SO THAT THE PLANT'S NATURAL ROOT COLLAR OR CROWN IS ABOVE FINISHED GRADE AT THE HEIGHTS INDICATED IN THE PLANTING DETAILS. NO BURLAP SHALL BE PULLED FROM UNDER THE BALLS. ROOTS ON BARE-ROOT PLANTS SHALL BE SPREAD IN THEIR NORMAL POSITION. ALL BROKEN OR FRAYED ROOTS SHALL BE CUT OFF CLEANLY. PREPARED SOIL SHALL BE PLACED AND COMPACTED CAREFULLY TO AVOID INJURY TO ROOTS. TO FILL ALL VOIDS. AND TO MINIMIZE ROCKING OF ROOT BALL. ADD WATER AND TAMP THE BACKFILL UNTIL THE BACKFILL IS COMPLETELY SATURATED. THEN ALLOW IT TO SOAK AWAY. FILL THE HOLE TO FINISHED GRADE, AND FORM A SHALLOW SAUCER AROUND EACH TREE AND SHRUB BY PLACING A RIDGE OF TOPSOIL AROUND THE EDGE OF EACH PIT. AFTER THE GROUND SETTLES, ADDITIONAL SOIL SHALL BE FILLED IN TO THE LEVEL OF THE FINISHED

12) STAKING TREES: DO NOT STAKE TREES, UNLESS TREES ARE PLANTED ON STEEP SLOPES, IN WHICH CASE THE CONTRACTOR SHALL CONTACT THE LANDSCAPE ARCHITECT FOR PERMISSION TO STAKE THOSE TREES.

13) MAINTENANCE: MAINTAIN PLANTS AND PLANT BEDS FROM THE TIME OF INSTALLATION UNTIL THE FINAL INSPECTION IMMEDIATELY PRIOR TO COMMENCEMENT OF THE GUARANTEE PERIOD. MAINTENANCE SHALL INCLUDE WATERING AND PROTECTION OF PLANTINGS AND OTHER NECESSARY OPERATIONS.

14) FINAL INSPECTION: WHEN THE TREE AND SHRUB PLANTINGS ARE READY FOR FINAL INSPECTION, ALL MULCHED AREAS SHALL BE FREE FROM WEEDS AND MULCHED TO THE EXTENT INDICATED ON THESE DRAWINGS. PLANT TAGS SHALL BE REMOVED BY THE CONTRACTOR PRIOR TO THE INSPECTION FOR ACCEPTANCE.

15) GUARANTEE: AFTER ACCEPTANCE AT TIME OF FINAL INSPECTION, ALL PLANTS SHALL BE GUARANTEED FOR ONE (1) YEAR. PLANTINGS SHALL BE ALIVE AND IN SATISFACTORY VIGOR AT THE END OF THE GUARANTEE PERIOD.

16) REPLACEMENT: AT THE END OF THE GUARANTEE PERIOD, ANY PLANT REQUIRED UNDER THIS CONTRACT THAT IS DEAD OR IN POOR VIGOR SHALL BE REMOVED FROM THE SITE. THESE AND ANY MISSING PLANTS SHALL BE REPLACED AS SOON AS CONDITIONS PERMIT, BUT DURING THE NORMAL PLANTING SEASON. ALL REPLACEMENTS SHALL BE PLANTS OF THE SAME KIND AS ORIGINALLY PLANTED AND SHALL BE OF SIZE EQUAL TO THAT ATTAINED BY ADJACENT PLANTS OF THE SAME KIND AT THE TIME REPLACEMENT IS MADE. ONLY ONE REPLACEMENT WILL BE REQUIRED FOR EACH PLANT DECLARED DEAD, IN AN UNHEALTHY OR BADLY IMPAIRED CONDITION, OR MISSING AT THE TIME OF FINAL INSPECTION.





Andrews Survey & Engineering, Inc. Land Surveying - Civil Engineering - Site Planning


P.O. Box 312, 104 Mendon Street Uxbridge, Massachusetts 01569-0312 P: 508-278-3897 F: 508-278-2289

This drawing and the design are property of Andrews Survey & Engineering, Inc. and shall not be altered or reused in whole or part without the express written permission of Andrews Survey & Engineering, Inc. Copyright ©2014

		INDER SITE F IING BOARD	LAN R	EVIEW.	
-	PEING A MA	IORITY	DATE		
<u> </u>		<u>JORITY</u>			
		UNDER SITE F ANNING BOAR		EVIEW.	
-					
-					
- 8	BEING A MA	JORITY .	DATE		
PROJECT:	THE COLLINGS FOUNDATION SITE DEVELOPMENT PLAN	137 BARTON ROAD STOW, MA 01775	APPLICANT:	COLLINGS FOUNDATION, INC. P.O. BOX 248 STOW, MA 01775	
NO	. DATE	REVI		CRIPTION	
				7.5	
CA	D FILE				
_	AWN BY	AWW			
СН	ECKED BY	AWW			
DA		JANUARY 20, 2015			
אין	PROJECT NO. 2014-021 GRAPHIC SCALE			F	
_		UNAFAI	JUAL	-	

LANDSCAPE DETAILS AND NOTES

SHEET TITLE



L-5.3

DRAWING NO.